

Madison-Walnut-Washington Sewer Separation Project

Project Owner:	City of Portland
Sewershed:	Back Cove
CSO's Impacted:	019 Diamond St-Back Cove
Year Contracted:	2017
Bid Amount:	2017 Estimated at \$1,942,000
Bid Date:	September 7 th 2017
Prime Consultant:	To be Determined
Prime Contractor:	Will be determined upon bidding
Sewershed:	Back Cove

Project Overview:

The project will be executed by the installation of approximately 1,400 lateral feet of storm drain and 15 new catch basins within the proposed project area. The diameters of the pipes will range from 10 to 18 inches.

Included in this project is the replacement of sanitary sewer lines as well as sewer laterals within the project location. This involves the installation of 23 new manholes consisting of various sizes.

Through this project, the city will be effectively removing 16.58 acres of drainage area from the combined sewer shed # 19 Diamond Street at Back Cove.

Finally, the roadway configuration will be restored with curbing alterations, pedestrian crossings, and traffic striping.



Extent of Project Location